

The Muon Veto @ GERDA

GERDA Collaboration

Tübingen, November 9-11, 2005

Peter Grabmayr



EBERHARD KARLS

UNIVERSITÄT
TÜBINGEN



P. Grabmayr

Muon veto




Components:

- *water in tank(s) + scintillator*
- *3rd wall + reflector (VM2000)*
- *photomultiplier ETL 8" 9350KB*
- *encapsulation*
- *cables, flange, splitter*
- *electronics, DAQ*

Time table

The setup

flux at LNGS: $1,1 \mu\text{/h/m}^2 \rightarrow 100 \mu\text{/h}$
 $1,4 \cdot 10^8 \mu$ simulated $\equiv 1,4 \cdot 10^6 \text{ h} = 160 \text{ yr}$



260 μ are dangerous


$$r = 1,9 \cdot 10^{-6}$$

$\varepsilon_C = 97\%$ feasible

in water, coverage of 0,7%,
reflectivity $\sim 0,9$
 $n \sim 0,6 \text{ pe/cm}$

scintillator panel

Light collection with fibers




04.02.05

V.Egorov JINR

reflector foil & wavelength shifter

radiant mirror foil VM2000 by 3M




all walls ?
ph value of water


The PMT encapsulation

Borexino type (Veto)

stainless steel, passivated; PET window



filled with oil



The PMT encapsulation

Borexino type (Veto)




DChooz reproduce radio assay; large geometrical variations; μ metal
P. Grabmayr

connectors & cables

connector “Jupiter” water tight $\Phi = 10,8\text{mm}$

(Note: RG58 $\Phi = 5$, mm, not watertight)




Huber+Suhner: water tight coating PUR

- G_12112: $\Phi = 18\text{mm}$, $V_{max.op} = 12\text{ kV}$, $\tau = 4,13\text{ns/m}$
- S_07212: $\Phi = 10,8\text{mm}$, $V_{max.op} = 1,05\text{kV}$, $\tau = 5,03\text{ns/m}$

total of 2km cables in water tank

Layout for cables

several flanges for cables
service flanges



equal length PMT \longleftrightarrow flange

Time table



Components in house:

- 30 PMT 9354KB delivered (ultra-low background)
- 1 roll of VM2000
- basic electronic moduls VME + crate
- quotations for encapsulation, pressure tank
- quotations for cables+connectors
-

Time table

- Dec 2005:
 - delivery of 70 PMT 9350KB (low background)
 - 2 prototype of housing
 - decision about cables, connectors, HV
- Feb 2006:
 - pressure tank operational
 - test of PMT encapsulation
- summer 2006:
 - mass production + testing
- fall 2006:
 - shipping to LNGS
 - mounting inside water tank AFTER pressure test of tank
 - cabling + DAQ test

3rd wall - draft

